

Determining the Octant of θ_{23} with PINGU, T2K, NO ν A and Reactor Data

Sandhya Choubey*, Anushree Ghosh[†]

^a*Harish-Chandra Research Institute, Chhatnag Road, Jhansi, Allahabad 211 019, India*

November 13, 2018

Abstract

We explore the prospects of determining the octant of θ_{23} with atmospheric neutrinos at PINGU. We study in detail the impact of energy and angle resolutions of the neutrino on the octant sensitivity. We show that the systematic uncertainties on the atmospheric neutrino flux predictions, especially the ones which affect the energy and zenith angle spectrum of the neutrinos, make a rather drastic reduction of the sensitivity of PINGU. We also study the prospects of measuring the octant of θ_{23} in the long baseline experiments T2K and NO ν A in conjunction with the reactor experiments. We study this for two configurations of NO ν A and T2K and make a comparative analysis of them. From just 3 years of PINGU data, the octant could be determined at more than 3σ C.L. for $\sin^2\theta_{23} < 0.419$ and $\sin^2\theta_{23} > 0.586$ if we add the reactor data and if normal hierarchy is true. On addition of the data from T2K and NO ν A, the sensitivity improves so that the octant could be determined at the 4σ C.L. for $\sin^2\theta_{23} < 0.426$ and $\sin^2\theta_{23} > 0.586$ if normal hierarchy is true. Even a 5σ significance for the right octant can be achieved if $\sin^2\theta_{23}(\text{true}) < 0.413$ for the true normal hierarchy. The sensitivity for the true inverted hierarchy is lower and we expect a 3σ determination of octant of θ_{23} for $\sin^2\theta_{23}(\text{true}) < 0.43$ and > 0.585 from the combined data set for this case.

1 Introduction

PINGU [1] (Precision IceCube Next Generation Upgrade) has been proposed as a low energy extension of the already existing and successfully running IceCube detector [2]. While the energy threshold of the full IceCube detector is 100 GeV, PINGU is envisioned to have an energy threshold of a few GeV, thereby allowing it to function as a low energy atmospheric neutrino experiment, with an effective fiducial mass in the multi-megaton range. The plan is to increase the number of strings, increasing the optical module density, and hence increasing the photo-coverage of the region. This will reduce the energy threshold for the detection of the muons. The number of optical modules have already been increased for the

*email: sandhya@hri.res.in

[†]email: anushree@hri.res.in

existing IceCube Deep Core (ICDC) area of the detector which has an energy threshold of 10 GeV and which has already released its first data on atmospheric neutrinos with energies greater than 10 GeV [3]. The ICDC has 8 extra strings in addition to the 7 strings belonging to the original IceCube design, providing a string spacing of about 75m. The plan is to increase the string density by putting 20 to 40 additional strings. The 20 string option would allow for 26m spacing between strings. The 40 string option will obviously have a larger effective area compared to the 20 string option and possibly a lower energy threshold, and hence will give better results. The large fiducial mass gives PINGU an edge over other competitive experiments. The potential of measuring the neutrino mass hierarchy at PINGU has been studied by quite a few groups [4, 5, 7, 6, 8, 9, 10].

Amongst the other issues in neutrino physics that remain to be probed, is the determination of the octant of θ_{23} mixing angle, in case it is found to be different from maximal. Various ways have been suggested in the literature to determine the octant of θ_{23} in the current and next generation neutrino oscillation experiments. One easy way is to combine the data from reactor experiments with the ν_e -appearance data from conventional accelerator experiments [11, 12, 13]. The reactor experiments return a pure measurement of the mixing angle $\sin^2 2\theta_{13}$, while the ν_e -appearance data from conventional accelerator experiments measure the combination $\sin^2 \theta_{23} \sin^2 2\theta_{13}$, at leading order. Using this combined analysis, one could then extract information on the octant of θ_{23} . Another approach studied in the literature has been to combine the ν_e -appearance channel in long baseline experiments with the ν_μ -disappearance channel [14, 15]. The upshot of this reasoning is that the best-fit θ_{23} preferred by the appearance channel is different from the best-fit θ_{23} favored by the disappearance channel. This generates a synergy between the two data sets in the long baseline experiment, leading to an octant sensitivity. The third way is to use Δm_{21}^2 dependent terms in the oscillation probability, which depend on either $\sin^2 \theta_{23}$ or $\cos^2 \theta_{23}$, leading to θ_{23} octant sensitivity. This was shown in the context of sub-GeV ν_e -events from atmospheric neutrinos at a water Cerenkov experiment like Super-Kamiokande [16] where the Δm_{21}^2 driven oscillatory terms bring in an octant of θ_{23} dependence in the low energy electron event sample. Finally, one can use the octant of θ_{23} dependence in the earth matter effects in the $P_{\mu\mu}$ channel to get a measure on this parameter [17]. Determining the octant of θ_{23} through observation of earth matter effects in $P_{\mu\mu}$ channel has been studied for atmospheric neutrino experiments with magnetized iron detectors [17, 18, 19], water Cerenkov detectors [20] and liquid argon detectors [15, 21, 22].

In this paper, we mainly focus at the prospects of determining the octant of θ_{23} through observation of earth matter effects in megaton-class Cerenkov detectors. In particular, we will work with the PINGU set-up, though our results are also valid for ORCA (Oscillation Research with Cosmics in the Abyss) [23], with suitable adjustments for the detector specifications like effective volume, reconstruction efficiency and energy and angle resolutions. The physics potential of PINGU has been studied in [4, 5, 7, 6, 8, 9, 10]. In particular, the issue of determining the octant of θ_{23} was briefly discussed in [5]. Here, we will present detailed analysis of the reach of the PINGU experiment towards the determination of the octant of θ_{23} , taking into account the detector specifications provided by the PINGU collaboration, as well as after including full systematic uncertainties on the atmospheric neutrino fluxes. We will show in detail how the projected reach of PINGU changes with the energy and angle resolution, as well as with the inclusion of the systematic uncertainties in the analysis. We will also study how the sensitivity to determination of the octant of θ_{23} at PINGU goes down when one marginalizes over the oscillation parameters $|\Delta m_{31}^2|$, $\sin^2 \theta_{13}$, $\sin^2 \theta_{23}$ and the neutrino mass hierarchy.¹

¹Note that the sensitivity to the octant of θ_{23} at PINGU is almost insensitive to the value of δ_{CP} and so we take

Since the Daya Bay, RENO, Double Chooz and T2K experiments are already operational and since NO ν A will also start operations soon, it is expected that we will have full or at least partial data from these experiments by the time we have enough data collected at PINGU. In addition, sizable octant sensitivity is expected from the combined results from T2K, NO ν A and the reactor experiments as discussed above. Therefore, we will use the projected data from these experiments to give the sensitivity to the octant of θ_{23} from these experiments combined with PINGU. The combination of the data from the long baseline and reactor experiments to the PINGU data serves four purposes. Firstly, we can compare and contrast the prospects of determining the octant of θ_{23} at PINGU versus the prospects expected from the current accelerator and reactor experiments. Secondly, a combined analysis of PINGU with the accelerator and reactor experiments shows possible synergies between the different experiments. Thirdly and most importantly, the accelerator and reactor experiments severely constrain the oscillation parameters $|\Delta m_{31}^2|$, $\sin^2 2\theta_{23}$ and $\sin^2 2\theta_{13}$. This reduces the effect of marginalization in PINGU, thereby increasing the χ^2 . Finally, the net sensitivity to the octant of θ_{23} will anyway be given by a global analysis of all available neutrino oscillation data after a few years of running of PINGU, and our aim in this paper is to show this.

A discussion on the role of δ_{CP} in the analysis of the data from long baseline experiment is in order. The sensitivity of the LBL experiments to the octant of θ_{23} depends on the true value of the CP phase, $\delta_{CP}(\text{true})$. This was studied in detail in [14, 15] where the octant sensitivity of the combined NO ν A and T2K data was shown as a function of the $\delta_{CP}(\text{true})$. In particular, in [14], the authors showed the degeneracy between θ_{23} and δ_{CP} , and since the value of δ_{CP} is completely unknown, the octant of θ_{23} sensitivity from long baseline experiments suffers. They showed that running T2K in the antineutrino mode alleviates this $\delta_{CP} - \theta_{23}$ degeneracy issues. In particular, they compared results of 5 years of neutrino running alone in T2K [24], against those obtained with 2.5 years in neutrino and 2.5 years in the antineutrino mode, and argued that the 2.5+2.5 years option for T2K was better. This issue was also recently pointed out and studied in [25]. We will also show our results for both possibilities for T2K. The NO ν A experiment has recently re-optimized [26] their event selection criteria, following the discovery of large θ_{13} [27, 28, 29, 30, 31]. We have used this new NO ν A configuration following [32] and have compared the results using the new NO ν A configuration versus the old NO ν A configuration [33]. For both NO ν A configurations we use 3+3 years of running of the experiment in the neutrino+antineutrino mode. A final comment is in order. The recent studies on the octant of θ_{23} sensitivity from long baseline experiments [14, 15], imposed a prior on the value of θ_{13} in the fit and showed that the octant sensitivity of the long baseline experiments depends crucially on that. In this work we add the projected reactor data from the full 3 years run of Daya Bay [34], RENO [35] and Double Chooz [36].

The paper is organized as follows. We start in section 2 with a description of the atmospheric neutrino events in PINGU and our method of the analysis of the simulated data in PINGU. In section 3 we present the octant sensitivity from PINGU alone, allowing for full marginalization of the oscillation parameters. We discuss in detail the impact of detector resolutions, systematic uncertainties and uncertainties in oscillation parameters on the final octant sensitivity at PINGU. In section 4 we begin with a discussion of the octant sensitivity of T2K+NO ν A+Reactor experiments. We compare and contrast the reach of old NO ν versus new NO ν A configuration. We also make a comparative study of the octant

$\delta_{CP}(\text{true}) = 0$ in the simulated data for PINGU throughout this paper. For results that use only the PINGU data, we keep $\delta_{CP} = 0$ fixed in the fit as well. In this paper we will denote the true values of the oscillation parameters by putting ‘true’ within brackets.

sensitivity with 5 years of T2K running in the neutrino mode alone vis-a-vis 2.5 years of T2K running in neutrino and remaining 2.5 years of T2K running in the antineutrino mode. Finally, we show the octant of θ_{23} sensitivity coming from combined fits of the PINGU data along with the projected runs of the T2K+NO ν A+Reactor experiments. We end in section 5 with our conclusions.

2 Atmospheric Neutrinos in PINGU

The number of atmospheric muon events expected in PINGU after T years of running of the experiment is given as

$$\begin{aligned}
(N_\mu)_{ij} = & 2\pi N_T T \int_{(\cos \Theta)_i}^{(\cos \Theta)_{i+1}} d \cos \Theta \int_{E_j}^{E_{j+1}} dE \epsilon \rho_{ice} V_{eff}(E) \times \\
& \left[\left(\frac{d^2 \phi_{\nu_\mu}}{d \cos \Theta' dE'} P_{\mu\mu} + \frac{d^2 \phi_{\nu_e}}{d \cos \Theta' dE'} P_{e\mu} \right) \sigma_{CC}(E) + \right. \\
& \left. \left[\left(\frac{d^2 \phi_{\bar{\nu}_\mu}}{d \cos \Theta' dE'} P_{\bar{\mu}\bar{\mu}} + \frac{d^2 \phi_{\bar{\nu}_e}}{d \cos \Theta' dE'} P_{\bar{e}\bar{\mu}} \right) \right] \sigma_{CC}(E) \right] \quad (1)
\end{aligned}$$

where N_T are the number of targets in the detector, T is the exposure time, ϵ is the detector efficiency, $\rho_{ice} V_{eff}$ is the effective mass of the detector, V_{eff} is the effective volume, $d^2 \phi_\alpha / dE' d \cos \Theta'$ is the neutrino flux of flavor α [37], $\sigma_{CC}(E)$ is the neutrino-nucleon interaction cross-section, $R(E, E')$ and $R(\Theta, \Theta')$ are the energy and angle resolution functions of the detector respectively, and $P_{\mu\mu}$ and $P_{e\mu}$ are the muon neutrino survival probability and electron neutrino to muon neutrino conversion probabilities, respectively. The resolution functions relate the true energy E' and zenith angle Θ' with the reconstructed energy E and zenith angle Θ , of the neutrino. We assume Gaussian functional form for the resolutions functions with widths

$$\sigma_E = a + bE', \quad \sigma_\Theta = c \cdot \sqrt{\frac{1 \text{ GeV}}{E'}}. \quad (2)$$

Since the final resolution widths for PINGU is still being estimated from detailed simulations, we will assume two sets of values for the energy resolution width σ_E corresponding to $a = 0$, $b = 0.2$ and $a = 2$, $b = 0$, and two sets of values for the angle resolution width σ_Θ corresponding to $c = 1$ and $c = 0$, where c (and hence σ_Θ) is in radians. These values for the resolution functions agree with that used in the literature [4, 8, 9]. The effective mass of the detector is read from [38] for the curve labelled ‘‘Triggered Effective Volume, R=100m’’. The probabilities $P_{\mu\mu}$ and $P_{e\mu}$ are calculated numerically solving the propagation equation of the neutrinos through the atmosphere and inside the earth, and using the PREM profile [39] for the earth matter density. For simplicity we take $\epsilon = 1$, since any flat ϵ can be easily adjusted against the exposure taken at the detector. The index i in Eq. (1) runs over the number of $\cos \Theta$ bins in the data while j runs over the number of energy bins. In the analysis presented in this paper, we have taken 10 equal zenith angle bins in $\cos \Theta$ between $\cos \Theta = -1$ and 0, and 7 equal energy bins between $E = 2$ and 14 GeV. The data is generated for the oscillation parameters given in Table 1 for either the normal or inverted hierarchy and for a given value of $\sin^2 \theta_{23}$. Note that we use $\Delta m_{\text{eff}}^2 > 0$ as our definition of the normal mass hierarchy and $\Delta m_{\text{eff}}^2 < 0$ as inverted mass hierarchy, where

$$\Delta m_{\text{eff}}^2 = \Delta m_{31}^2 - (\cos^2 \theta_{12} - \cos \delta_{CP} \sin \theta_{13} \sin 2\theta_{12} \tan \theta_{23}) \Delta m_{21}^2, \quad (3)$$

The simulated data is then fitted with the wrong octant solution of $\sin^2 \theta_{23}$, allowing the test $|\Delta m_{\text{eff}}^2|$, $\sin^2 \theta_{13}$, $\sin^2 \theta_{23}$ as well as the neutrino mass hierarchy to vary in the fit. The statistical fit is performed using a χ^2 function defined as

$$\chi^2 = \min_{\{\xi_j\}} \sum_{ij} \left[\frac{(N_{ij}^{th} - N_{ij}^{ex})^2}{N_{ij}^{ex}} \right] + \sum_{s=1}^k \xi_s^2, \quad (4)$$

$$N_{ij}^{th} = N_{ij} \left(1 + \sum_{s=1}^k \pi_{ij}^s \xi_s \right) + \mathcal{O}(\xi_s^2), \quad (5)$$

where N_{ij}^{ex} is the observed number of muon events in the i^{th} $\cos \Theta$ and j^{th} energy bin and N_{ij}^{th} is the corresponding theoretically predicted event spectrum for the wrong octant solution of θ_{23} . The π_{ij}^s in Eq. (5) is the ij^{th} systematic uncertainty in the i^{th} $\cos \Theta$ and j^{th} energy bin and ξ_s is the pull variable corresponding to the uncertainty π_{ij}^s . We have included five systematic uncertainties in our analysis. They are, an overall flux normalization error of 20%, a cross-section uncertainty of 10%, a 5% uncertainty on the zenith angle dependence of the fluxes, an energy dependent ‘‘tilt factor’’, and a 5% additional overall uncertainty. The parameters $|\Delta m_{\text{eff}}^2|$ and $\sin^2 \theta_{13}$ are varied freely in the fit in the range given in Table 1. For $\sin^2 \theta_{23}$, we marginalize around $\Delta \sin^2 \theta_{23} \pm 0.1$ around the wrong octant $\sin^2 \theta_{23}$ for any given $\sin^2 \theta_{23}(\text{true})$. Finally, the χ^2 is computed for both the test hierarchies and the minimum χ^2 chosen.

Parameter	True value used in data	3σ range used in fit
Δm_{21}^2	$7.5 \times 10^{-5} \text{ eV}^2$	$[7.0 - 8.0] \times 10^{-5} \text{ eV}^2$
$\sin^2 \theta_{12}$	0.3	[0.265 - 0.33]
$ \Delta m_{\text{eff}}^2 $	$2.4 \times 10^{-3} \text{ eV}^2$	$[2.1 - 2.6] \times 10^{-3} \text{ eV}^2$
δ_{CP}	0	[0 - 2π]
$\sin^2 2\theta_{13}$	0.1	[0.07 - 0.13]

Table 1: Benchmark true values of oscillation parameters used in the simulations, unless otherwise stated. The range over which they are allowed to vary freely in the fit is also shown in the last column. For $\sin^2 \theta_{23}(\text{true})$ we marginalize around $\Delta \sin^2 \theta_{23} \pm 0.1$ around the wrong octant $\sin^2 \theta_{23}$ for any given $\sin^2 \theta_{23}(\text{true})$. For PINGU alone analysis we keep Δm_{21}^2 , $\sin^2 \theta_{12}$ and δ_{CP} fixed at their true values.

3 Octant Sensitivity from PINGU Alone

The results of our statistical analysis and the sensitivity of PINGU *alone* to the octant of θ_{23} is given in Fig. 1, where we have shown the $\Delta\chi^2$ as a function of $\sin^2 \theta_{23}(\text{true})$. We have used 3 years of running of the experiment with the effective mass of the detector read from [38] for the curve labelled ‘‘Triggered Effective Volume, R=100m’’. The left panels of this figure give the octant sensitivity when the data is




Figure 1: $\Delta\chi^2$ for the wrong octant obtained from just the PINGU data with 3 years statistics, as a function of $\sin^2\theta_{23}(\text{true})$. The left panel is for normal hierarchy taken as true while the right panel is for inverted hierarchy taken as true. In the top panels, the χ^2 is marginalized over the oscillation parameters, $|\Delta m_{\text{eff}}^2|$, $\sin^2 2\theta_{13}$ and $\sin^2\theta_{23}$ as described in the text, but the mass hierarchy is held fixed to the assumed true case in the fit. In the bottom panels, the χ^2 is marginalized over the oscillation parameters, $|\Delta m_{\text{eff}}^2|$, $\sin^2 2\theta_{13}$ and $\sin^2\theta_{23}$, as well as the mass hierarchy, keeping mass hierarchy free in the fit. The four lines are for the four possible combinations for the choices of the energy and angle resolution of PINGU.

generated assuming the normal hierarchy ($\Delta m_{\text{eff}}^2 > 0$), while the right panels are obtained when the data is generated assuming the inverted mass hierarchy ($\Delta m_{\text{eff}}^2 < 0$). We have included the full flux systematic uncertainties as outlined in the previous section. The top panels are obtained when the χ^2 is marginalized over the oscillation parameters, $|\Delta m_{\text{eff}}^2|$, $\sin^2 2\theta_{13}$ and $\sin^2 \theta_{23}$ as described in the previous section, however, the test mass hierarchy is kept fixed at the assumed true value. The bottom panels are obtained when in addition to $|\Delta m_{\text{eff}}^2|$, $\sin^2 2\theta_{13}$ and $\sin^2 \theta_{23}$, the $\Delta\chi^2$ is marginalized also with respect to the mass hierarchy. The four lines are for the four possible combinations for the energy and angle resolutions of PINGU. The red dashed lines are for *our* optimal choice of $\sigma_E = 0.2E'$ and $\sigma_\Theta = 0.5 (1 \text{ GeV}/\sqrt{E'})$, as discussed in section 2.

This figure shows the impact of a variety of things on the octant sensitivity at PINGU. Let us start by looking at the impact of the resolution functions on the octant sensitivity. From the top left panel, we find that if the normal hierarchy was true and the test hierarchy was kept fixed as normal, then the wrong θ_{23} octant could be ruled out at more than 3σ C.L. ² if $\sin^2 \theta_{23}(\text{true}) < 0.424$ and $\sin^2 \theta_{23}(\text{true}) > 0.588$ if $\sigma_E = 0.2E'$ and $\sigma_\Theta = 0.5 (1 \text{ GeV}/\sqrt{E'})$. To show the impact of the resolution functions on the octant sensitivity, we have repeated the exercise for different combinations of σ_E and σ_Θ . Keeping $\sigma_\Theta = 0.5/\sqrt{E'}$ and changing σ_E from $0.2E'$ to 2 GeV reduces the statistical significance of the octant measurement and now we expect 3σ sensitivity for $\sin^2 \theta_{23}(\text{true}) < 0.416$ and $\sin^2 \theta_{23}(\text{true}) > 0.6$. The impact of worsening of the zenith angle sensitivity is seen to be sharper. Keeping $\sigma_E = 0.2E'$ if we change $\sigma_\Theta = 0.5\sqrt{1 \text{ GeV}/E'}$ to $\sigma_\Theta = 1.0\sqrt{1 \text{ GeV}/E'}$, this reduces the statistical significance of the octant measurement significantly and now we have only 2σ sensitivity for $\sin^2 \theta_{23}(\text{true}) < 0.412$ and $\sin^2 \theta_{23}(\text{true}) > 0.588$. For the case where both energy resolution and angle resolutions are worsened to $\sigma_E = 2 \text{ GeV}$ and $\sigma_\Theta = 1.0\sqrt{1 \text{ GeV}/E'}$, we find that the wrong octant can be ruled out only at 2σ for $\sin^2 \theta_{23}(\text{true}) < 0.4$ and $\sin^2 \theta_{23}(\text{true}) > 0.6$.

The right panels of Fig. 1 show the sensitivity of PINGU alone to the octant of θ_{23} if the inverted hierarchy was true. We find that for the inverted hierarchy the sensitivity falls significantly, and even for $\sin^2 \theta_{23}(\text{true}) = 0.4$, the wrong hierarchy would be barely ruled at the 2σ C.L.. The sharp difference between the reach of the experiment to the octant of θ_{23} between the normal and inverted hierarchy can be understood as follows. Let us say that we generate the data at a certain value of θ_{23} and fit the data for $\theta_{23}(\text{fit})$. Since the main sensitivity of PINGU to the octant of θ_{23} comes from earth matter effects, for normal hierarchy the difference between number of events for θ_{23} and $\theta_{23}(\text{fit})$ is expected to be non-zero for the neutrino events and nearly zero for the antineutrino events. In that case, since PINGU cannot distinguish between the particle and antiparticle, the χ^2 obtained for normal hierarchy can be very roughly written as

$$\chi^2(NH) \sim \frac{(N_{\mu^-}^{NH}(\theta_{23}) - N_{\mu^-}^{NH}(\theta_{23}^{\text{fit}}))^2}{N_{\mu^-}^{NH}(\theta_{23}) - N_{\mu^+}^{NH}(\theta_{23})}, \quad (6)$$

where for simplicity, we have neglected the systematic uncertainties and have assumed the test hierarchy to be fixed. The same argument holds in the general case. In Eq. 6 we have taken $N_{\mu^+}^{NH}(\theta_{23}) - N_{\mu^+}^{NH}(\theta_{23}^{\text{fit}}) \simeq 0$, since for normal hierarchy there are almost no earth matter effects in the antineutrino channel. On the other hand for the inverted hierarchy the corresponding χ^2 is approximately given as

$$\chi^2(IH) \sim \frac{(N_{\mu^+}^{IH}(\theta_{23}) - N_{\mu^+}^{IH}(\theta_{23}^{\text{fit}}))^2}{N_{\mu^-}^{IH}(\theta_{23}) - N_{\mu^+}^{IH}(\theta_{23})}, \quad (7)$$

²Where the number of σ n is defined as $n\sigma = \sqrt{\Delta\chi^2}$.

since in the case of the inverted hierarchy the difference between the number of events $N_{\mu^-}^{IH}(\theta_{23}) - N_{\mu^-}^{IH}(\theta_{23}^{fit}) \simeq 0$, as for this case there are almost no earth matter effects in the neutrino channel. We can very approximately write

$$\left(N_{\mu^-}^{NH}(\theta_{23}) - N_{\mu^-}^{NH}(\theta_{23}^{fit}) \right) \simeq \Delta P_{\mu\mu}^{NH} N_{\mu^-}^0 + \Delta P_{e\mu}^{NH} N_{e^-}^0, \quad (8)$$

where $N_{\mu^-}^0$ and $N_{e^-}^0$ are the number of ν_{μ^-} -events and ν_{e^-} -events in absence of oscillations and

$$\begin{aligned} \Delta P_{\mu\mu}^{NH} &= P_{\mu\mu}^{NH}(\theta_{23}) - P_{\mu\mu}^{NH}(\theta_{23}(fit)), \\ \Delta P_{e\mu}^{NH} &= P_{e\mu}^{NH}(\theta_{23}) - P_{e\mu}^{NH}(\theta_{23}(fit)). \end{aligned} \quad (9)$$

For the inverted hierarchy case we have

$$(N_{\mu^+}^{IH}(\theta_{23}) - N_{\mu^+}^{IH}(\theta_{23}^{fit})) \simeq N_{\mu^+}^0 \Delta P_{\bar{\mu}\bar{\mu}}^{IH} + N_{e^+}^0 \Delta P_{\bar{e}\bar{\mu}}^{IH}, \quad (10)$$

where $N_{\mu^+}^0$ and $N_{e^+}^0$ are the number of $\bar{\nu}_{\mu}$ -events and $\bar{\nu}_e$ -events in absence of oscillations and $\Delta P_{\bar{\mu}\bar{\mu}}^{IH}$ and $\Delta P_{\bar{e}\bar{\mu}}^{IH}$ are given by

$$\begin{aligned} \Delta P_{\bar{\mu}\bar{\mu}}^{IH} &= P_{\bar{\mu}\bar{\mu}}^{IH}(\theta_{23}) - P_{\bar{\mu}\bar{\mu}}^{IH}(\theta_{23}(fit)), \\ \Delta P_{\bar{e}\bar{\mu}}^{IH} &= P_{\bar{e}\bar{\mu}}^{IH}(\theta_{23}) - P_{\bar{e}\bar{\mu}}^{IH}(\theta_{23}(fit)). \end{aligned} \quad (11)$$

Since

$$\Delta P_{\mu\mu}^{NH} \simeq \Delta P_{\bar{\mu}\bar{\mu}}^{IH} \quad \text{and} \quad \Delta P_{e\mu}^{NH} \simeq \Delta P_{\bar{e}\bar{\mu}}^{IH} \quad (12)$$

and

$$N_{\mu^+}^0 \simeq \frac{1}{2} N_{\mu^-}^0 \quad \text{and} \quad N_{e^+}^0 \simeq \frac{1}{2} N_{e^-}^0 \quad (13)$$

we have from Eqs. (6) and (7)

$$\chi^2(IH) \sim \frac{1}{4} \cdot \chi^2(NH) \cdot \frac{N_{\mu^-}^{NH}(\theta_{23}) - N_{\mu^+}^{NH}(\theta_{23})}{N_{\mu^-}^{IH}(\theta_{23}) - N_{\mu^+}^{IH}(\theta_{23})}. \quad (14)$$

Since the number of neutrino (μ^-) events are more than twice the number of antineutrino (μ^+) events, and since due to earth matter effects $N_{\mu^-}^{NH} < N_{\mu^-}^{IH}$ for any value of θ_{23} ,

$$\frac{N_{\mu^-}^{NH}(\theta_{23}) - N_{\mu^+}^{NH}(\theta_{23})}{N_{\mu^-}^{IH}(\theta_{23}) - N_{\mu^+}^{IH}(\theta_{23})} < 1 \quad (15)$$

and from Eq. (14) we see that we expect

$$\chi^2(IH) < \frac{\chi^2(NH)}{4}. \quad (16)$$

This rough comparison between the expected octant sensitivity between normal and inverted mass hierarchy cases is seen to agree rather well with the results shown in Fig. 1, which have been obtained from




Figure 2: Impact of marginalization over the different oscillation parameters on the $\Delta\chi^2$ for the wrong octant obtained from just the PINGU data with 3 years statistics, as a function of $\sin^2\theta_{23}(\text{true})$. The left-panel is for data generated with normal hierarchy while the right-panel is for data generated with inverted hierarchy.

a detailed numerical computation.

Finally, a comparison of the upper panels with the lower panels of Fig. 1 shows the impact of marginalization over the test mass hierarchy in the fit. Let us first discuss the case where the data is generated for true inverted hierarchy. For the true inverted hierarchy case we can see from the figure that marginalization over the test mass hierarchy in the fit has no impact on the octant sensitivity of the experiment. However, for true normal hierarchy there is significant reduction in the $\Delta\chi^2$ for low values of $\sin^2\theta_{23}(\text{true})$. In particular, we can see that for $\sin^2\theta_{23}(\text{true}) = 0.4$ the statistical significance of the octant determination from 3 years of PINGU data alone, comes down from $\Delta\chi^2 = 16.75$ to $\Delta\chi^2 = 6.9$ for the optimal resolution case of $\sigma_E = 0.2E'$ and $\sigma_\Theta = 0.5 (1 \text{ GeV}/\sqrt{E'})$. For the other choices of the combination for σ_E and σ_Θ also we see a similar trend, wherein the data with true normal hierarchy is fitted with the wrong test inverted hierarchy and with a lower χ^2 , reducing thereby the octant sensitivity from PINGU alone. However, for $\sin^2\theta_{23}(\text{true}) > 0.44$ the marginalization over hierarchy does not have any impact what-so-ever on the octant sensitivity of PINGU, even for the case of true normal hierarchy.

Note from Fig. 1 that the $\Delta\chi^2$ is large for $\sin^2\theta_{23}(\text{true})$ significantly far from maximal mixing. However, the statistical significance falls very fast and nearly disappears for $\sin^2\theta_{23}(\text{true}) \gtrsim 0.45$ and $\sin^2\theta_{23}(\text{true}) \lesssim 0.55$. The main reason for this flat $\Delta\chi^2 \simeq 0$ between these two limiting regions of $\sin^2\theta_{23}(\text{true})$ is the marginalization over the mixing angle θ_{23} in the fit. We show the effect of marginalization on the octant of θ_{23} sensitivity in Fig. 2. We have shown this figure for $\sigma_E = 0.2E'$ and $\sigma_\Theta = 0.5 (1 \text{ GeV}/\sqrt{E'})$. The left-hand panel of this figure is for true normal hierarchy while the right-hand

panel is for true inverted hierarchy case. The blue long dot-dashed lines in the two panels of this figure are the same as the red dashed line in the bottom panels of Fig. 1, where the χ^2 is marginalized over all oscillation parameters in the range given in Table 1, as well as over the test neutrino mass hierarchy. The cyan long dot-dashed solid lines are obtained when all oscillation parameters are taken fixed in the fit. We find that in that case the sensitivity shows a remarkable improvement, especially for the true normal hierarchy case. For $\sin^2 \theta_{23}(\text{true}) = 0.4$ the $\Delta\chi^2$ jumps from about 7 for the fully marginalized case to more than 22 for the all parameter fixed case. For the true inverted hierarchy case, the difference between the fully marginalized line and the all parameters fixed line is less dramatic, with the difference coming only for values of $\sin^2 \theta_{23}(\text{true})$ close to maximal mixing. The other lines in this figure have been drawn by keeping only one oscillation parameter fixed at a time, leaving the others to vary. For the true inverted hierarchy case, maximum difference to the plots, qualitatively as well as quantitatively, comes on fixing θ_{23} in the fit, which is shown by the green dashed lines. Fixing of this parameter increases the octant sensitivity considerably in terms of the range of $\sin^2 \theta_{23}(\text{true})$ for which the wrong octant solution can be disfavored, and we get a sensitivity which is very close to what we would have obtained if all oscillation parameters were fixed. In particular, the $\Delta\chi^2$ now has a softer fall as we approach maximal mixing angle. For the true inverted hierarchy case, the right-hand panel reveals that fixing any of the other oscillation parameter or the neutrino mass hierarchy makes no impact on the $\Delta\chi^2$.

For the true normal hierarchy case, the effect of fixing one parameter at a time is seen to have a much richer behavior, especially for low $\sin^2 \theta_{23}(\text{true})$. This is because the effect of marginalization over the oscillation parameters as well the mass hierarchy is much larger for the true normal hierarchy case. In particular, for low values of $\sin^2 \theta_{23}(\text{true}) \lesssim 0.45$, we find that fixing the neutrino mass hierarchy (pink solid line) causes a significant increase in the $\Delta\chi^2$, as we had seen before in Fig. 1. Fixing $|\Delta m_{\text{eff}}^2|$ (red short dashed line) is also seen to give a similar change to the $\Delta\chi^2$. The reason for this is as follows. When we let the test hierarchy vary in the fit, the wrong inverted hierarchy is preferred by pushing the fit value of θ_{13} to its current allowed upper limit as given in Table 1, and by suitably adjusting the fit $|\Delta m_{\text{eff}}^2|$. When we fix $|\Delta m_{\text{eff}}^2|$, then this freedom is lost, and in that case even if we allow the test hierarchy to vary, the minima still comes for the test normal hierarchy. Therefore, the fixed $|\Delta m_{\text{eff}}^2|$ case looks very similar to the fixed hierarchy case. The other parameter which has a significant impact for low values of $\sin^2 \theta_{23}(\text{true})$ is θ_{13} . The black dot-dashed lines show that the $\Delta\chi^2$ increases when θ_{13} is fixed at its true value in the fit. This point is worth noting. The reason is that constraint on θ_{13} is expected to significantly improve with more data from the reactor experiments, particularly Daya Bay, as well as T2K and NO ν A. In the next section when we will add the reactor data to the PINGU data we will find a sensitivity curve very close to the one shown in this figure for fixed θ_{13} . Finally, as in the case of the true inverted hierarchy, fixing θ_{23} in the fit brings a large effect on the octant sensitivity of PINGU. In fact, for the high octant region of the curve, we see that only the θ_{23} parameter plays a role in the marginalization process.

In order to show the impact of the systematic uncertainties on the octant of θ_{23} sensitivity at PINGU, we plot in Fig. 3 the $\Delta\chi^2$ as a function of $\sin^2 \theta_{23}(\text{true})$, with (solid lines) and without (dashed lines) systematic uncertainties. For simplicity we show the plot for the case where the mass hierarchy is kept fixed at the true value in the fit. The widths of the resolution functions assumed for each case is shown in the figure legend. The upper panels in this figure are for the normal hierarchy case while the lower panels show the result for the true inverted hierarchy. We can see that for the normal hierarchy case, systematic uncertainties reduce the $\Delta\chi^2$ by a factor of about 3.5 when $\sigma_E = 0.2E'$ GeV (upper left-hand




Figure 3: Impact of systematic uncertainties on the $\Delta\chi^2$ for the wrong octant obtained from just the PINGU data with 3 years statistics, as a function of $\sin^2\theta_{23}(\text{true})$. The solid lines show the $\Delta\chi^2$ when systematic uncertainties are included, while the dashed lines are obtained when we do not include the systematic uncertainties. The assumption of the width of the resolution functions are shown in the figure legend. We show the results for all combinations of σ_E and σ_θ . The upper panels are for normal hierarchy while the lower panels are for inverted hierarchy. The test hierarchy is kept fixed at the true value for all cases.

panel) and for both $\sigma_{\Theta} = 0.5\sqrt{1/E'}$ and $\sigma_{\Theta} = 1\sqrt{1/E'}$. For the worse energy resolution case of $\sigma_E = 2$ GeV (upper right-hand panel) the systematic uncertainties reduce the $\Delta\chi^2$ by a factor of about 4.2 for $\sigma_{\Theta} = 0.5\sqrt{1/E'}$ and by a factor of about 7.5 for $\sigma_{\Theta} = 1\sqrt{1/E'}$. Notice that the impact of the systematic uncertainty increases as the energy and angle resolution of the detector deteriorates. For the inverted hierarchy case too, we can see a big reduction in the sensitivity due to the systematic uncertainties and the trend with the resolution functions is the same. Amongst the 5 systematic uncertainties that we have included in our analysis, the ones which bring about the most impact are the theoretical uncertainties in the atmospheric neutrino fluxes coming from the uncertainty in the energy spectrum (called "tilt error" above) and from the uncertainty in the zenith angle. The uncertainties do not cancel between different bins and brings about a rather drastic decline in the sensitivity of PINGU to the octant of θ_{23} .

4 Octant Sensitivity of PINGU Combined with Others Experiments

Sizable octant sensitivity is expected from the current accelerator and reactor experiments. In the light of large θ_{13} , the reach of the combined data from T2K and NO ν A towards the discovery of the true octant of θ_{23} has been studied before in [11, 12, 13] and more recently in [14, 15]. The configuration for NO ν A given in the earlier NO ν A DPR and used in [13] was revised last year following the discovery of the relatively large θ_{13} . The details of the modified configuration for NO ν A can be found in [26] and was used in [32] to show the significant improvement expected in the mass hierarchy sensitivity of NO ν A. This revised configuration was used in the context of octant of θ_{23} sensitivity from current long baseline experiments in [14]. In [14], the authors also studied the impact of running T2K for 2.5 years in the neutrino and 2.5 years in the antineutrino mode, on the octant of θ_{23} sensitivity. The T2K experiment is officially scheduled to run only in the neutrino mode for 5 years. However, efforts are on to determine optimized exposure times for T2K in neutrino mode vis-o-vis antineutrino mode. On the other hand, the reactor experiments Daya Bay, RENO and Double Chooz, are expected to tighten the constraint on θ_{13} , which as we had seen in the previous section, makes a significant difference to the octant sensitivity of PINGU. Accurate measurement of θ_{13} at the reactor experiments is also known to be crucial for the octant determination using the T2K and NO ν A experiments. In this section we will include the full 3 years run of each of the reactor experiments, Daya Bay, RENO and Double Chooz, and combine this with long baseline data from T2K and NO ν A. For NO ν A we consider 3 years of neutrino and 3 years of antineutrino run and compare results between the old and the revised configurations of this experiment, while for T2K we will show octant sensitivity plots for both 5 years running in only the neutrino mode and 2.5 years in neutrino and 2.5 years in the antineutrino mode. Simulations of the event rates and $\Delta\chi^2$ for the long baseline and reactor experiments have been performed using the GLOBES software [40]. Finally, we will combine the reactor and long baseline data with 3 years of PINGU data and present the octant of θ_{23} sensitivity expected from the global data set.

In Fig. 4 we show the impact of using the revised NO ν A configuration on the mass hierarchy sensitivity from the combined analysis of the projected data from T2K, NO ν A, Daya Bay, RENO and Double Chooz. The $\Delta\chi^2$ for the mass hierarchy sensitivity with the new NO ν A configuration is seen to agree well with a similar plot shown in [32], apart from the fact that we have used $\sin^2 2\theta_{13}(\text{true}) = 0.1$ for this plot while the $\sin^2 2\theta_{13}(\text{true})$ used in [32] was slightly lower. The other difference is that we have explicitly added the reactor data to constrain θ_{13} while the authors of [32] impose a prior on $\sin^2 2\theta_{13}$. The mass hierarchy sensitivity is seen to increase with the new NO ν A configuration. We also show in this plot the impact of running T2K for 2.5 years in the neutrino and 2.5 years in the antineutrino mode. The solid




Figure 4: The $\Delta\chi^2$ for mass hierarchy sensitivity as a function of $\delta_{CP}(\text{true})$ for different configurations of $\text{NO}\nu\text{A}$ and T2K. For all cases we have the full projected data set from Daya Bay, RENO and Double Chooz reactor experiments. The $\Delta\chi^2$ is fully marginalized over the oscillation parameter region as described in the Table 1.

lines are for 5 years of T2K in only neutrino mode, while the dashed lines are with the 2.5+2.5 years configuration. The mass hierarchy sensitivity is known to be almost independent of the addition of T2K data in the $\delta_{CP}(\text{true}) = [-\pi, 0]$ range for true normal hierarchy and $\delta_{CP}(\text{true}) = [0, \pi]$ range for true inverted hierarchy, where $\text{NO}\nu\text{A}$ gives very high sensitivity to the mass hierarchy. However, in the region $\delta_{CP}(\text{true}) = [0, \pi]$ for true normal hierarchy and the region $\delta_{CP}(\text{true}) = [-\pi, 0]$ for the true inverted hierarchy, the T2K data does play a major role in increasing the mass hierarchy sensitivity of the combined analysis synergetically. In this relevant region, it is seen from the figure that running T2K for 2.5 years in neutrino and 2.5 years in antineutrino mode will result in a small loss in the net mass hierarchy sensitivity.

The $\delta_{CP}-\theta_{23}$ degeneracy has been discussed recently in [14, 25]. It has been shown in these works that this degeneracy can be broken if one allows T2K to run partially in the antineutrino mode as well. We show the octant sensitivity from the combined analysis of $\text{NO}\nu\text{A}$, T2K and the reactor experiments Daya Bay, RENO and Double Chooz, in Fig. 5. The figure shows the $\Delta\chi^2$ for the wrong octant solution as a function of $\delta_{CP}(\text{true})$. The left-hand panels are for true normal hierarchy while the right-hand panels are for true inverted hierarchy. We show the octant sensitivity for two benchmark values of $\sin^2 \theta_{23}(\text{true}) = 0.4$ (upper panels) and $\sin^2 \theta_{23}(\text{true}) = 0.6$ (lower panels). Each of the $\Delta\chi^2$ shown are fully marginalized over $|\Delta m_{\text{eff}}^2|$, $\sin^2 \theta_{13}$, $\sin^2 \theta_{23}$, as well as the mass hierarchy. The black lines are for the combined analysis of the long baseline and reactor data with the old $\text{NO}\nu\text{A}$ configuration, while the red lines are with the new $\text{NO}\nu\text{A}$ configuration. The red lines in the Fig. 5 are always above the black lines for both hierarchies and for both the benchmark $\sin^2 \theta_{23}(\text{true})$ chosen. Therefore, the new $\text{NO}\nu\text{A}$ configuration is seen to perform better for the octant sensitivity as well. The comparison between the T2K set-up running for full 5 years in the neutrino mode alone (solid lines) with that where T2K is run for 2.5 years in neu-




Figure 5: The $\Delta\chi^2$ for the octant sensitivity as a function of $\delta_{CP}(\text{true})$ for different configurations of NO ν A and T2K. For all cases we have the full projected data set from Daya Bay, RENO and Double Chooz reactor experiments. The $\Delta\chi^2$ is fully marginalized over the oscillation parameter region as described in the Table 1, as well as the mass hierarchy. The upper panels are for $\sin^2\theta_{23}(\text{true}) = 0.4$ while the lower panels are for $\sin^2\theta_{23}(\text{true}) = 0.6$. The left-hand panels are for true normal hierarchy while the right-hand panels are for true inverted hierarchy.

trino and 2.5 years in the antineutrino mode (dashed lines) is also shown in this figure. While the T2K 2.5+2.5 years set-up is seen to reduce the $\Delta\chi^2$ for $\delta_{CP}(\text{true})$ values where the octant sensitivity of the combined long baseline and reactor data was higher, it increases the $\Delta\chi^2$ in the $\delta_{CP}(\text{true})$ range where the sensitivity was lower. In particular, breaking up of the T2K running time from 5 years in neutrino to 2.5+2.5 years in neutrino+antineutrino mode reduces the fluctuation of $\Delta\chi^2$ as a function of $\delta_{CP}(\text{true})$.

The blue short-dashed lines in Fig. 5 are obtained when the T2K, NO ν A and the reactor data are combined with 3 years of data from the PINGU atmospheric neutrino experiment. We have used the PINGU configuration where $\sigma_E = 0.2E'$ and $\sigma_\Theta = 0.5 (1 \text{ GeV}/\sqrt{E'})$ and have included the 5 systematic uncertainties as discussed before. The PINGU data has almost no dependence on $\delta_{CP}(\text{true})$ and adds a constant $\Delta\chi^2$ constant contribution to the octant sensitivity of the global data. However, note that this additive contribution is more than what we were getting from PINGU alone. The increase in the $\Delta\chi^2$ from PINGU comes from the constraint on θ_{13} imposed by the reactor data and from the constraint on Δm_{eff}^2 and $\sin^2 2\theta_{23}$ from the long baseline data. This results in reducing the effect of marginalization over these parameters. This shows the synergy between PINGU and the long baseline and reactor data. If we were to add any further data set which could help in resolving the neutrino mass hierarchy, like the data from the INO atmospheric neutrino experiment [41], then this could further lift the $\Delta\chi^2$ for octant determination, for the low octant case ($\sin^2 \theta_{23}(\text{true}) = 0.4$) and for true normal hierarchy. For the high octant case for true normal hierarchy and for all cases for true inverted hierarchy, we had seen in the previous section that marginalization over the hierarchy made no difference and hence for these cases information on the neutrino mass hierarchy is not expected to bring any further improvement. We must stress here that addition of the INO data in the combined analysis will also improve the octant determination reach as INO itself has some octant sensitivity. However, we are not considering that possibility in this paper and this work will appear elsewhere [42]. For the true normal hierarchy, from the combined data from T2K, NO ν A, reactors and 3 years of PINGU, we expect a $\Delta\chi^2$ for the wrong octant solution between $\Delta\chi^2 = 26.8 - 31.9$ for $\sin^2 \theta_{23}(\text{true}) = 0.4$, depending on the value of $\delta_{CP}(\text{true})$ and between $\Delta\chi^2 = 19.9 - 24.1$ for $\sin^2 \theta_{23}(\text{true}) = 0.6$, depending on the value of $\delta_{CP}(\text{true})$. On the other hand, for the true inverted hierarchy, from the combined data from T2K, NO ν A, reactors and 3 years of PINGU, we expect a $\Delta\chi^2$ for the wrong octant solution between $\Delta\chi^2 = 17.6 - 23.8$ for $\sin^2 \theta_{23}(\text{true}) = 0.4$, depending on the $\delta_{CP}(\text{true})$ and between $\Delta\chi^2 = 12.8 - 16.7$ for $\sin^2 \theta_{23}(\text{true}) = 0.6$ depending on the $\delta_{CP}(\text{true})$.

The effect of combining the long baseline and reactor data with 3 years of PINGU data and the final combined sensitivity of the whole set-up together is shown in Fig. 6, as a function of $\sin^2 \theta_{23}(\text{true})$. We choose $\delta_{CP}(\text{true}) = 0$ to simulate the data for this figure. The left-panel of the figure is for true normal hierarchy while the right-panel is for true inverted hierarchy. Each of the curves shown in this figure have been fully marginalized in the way discussed before. The blue solid line shows the octant sensitivity of PINGU alone after marginalizing over oscillation parameters, including the neutrino mass hierarchy. Here we take $\sigma_E = 0.2E'$ and $\sigma_\Theta = 0.5\sqrt{E'}$ for PINGU, and full systematic uncertainties as discussed before. The blue dotted lines show the octant of θ_{23} sensitivity from 3 years of PINGU when the reactor data from 3 years of running of Daya Bay, RENO and Double Chooz are included in the analysis. The addition of the reactor data constrains the θ_{13} range, killing the effect of marginalization over this parameter and hence the $\Delta\chi^2$ increases for the low values of $\sin^2 \theta_{23}(\text{true})$. For the high octant side for true normal hierarchy and for all values of $\sin^2 \theta_{23}(\text{true})$ for the true inverted hierarchy, we do not see any improvement from the restriction on θ_{13} due the reactor data, as was discussed in the previous section (cf. Fig. 2).




Figure 6: $\Delta\chi^2$ for the wrong octant obtained from the combined analysis of 3 years of PINGU data with 3+3 years of running of (new) NO ν A, 5+0 years OR 2.5+2.5 years of running of T2K and 3 years of running of Daya Bay, RENO and Double Chooz. We show the combined sensitivity as a function of $\sin^2\theta_{23}(\text{true})$ for $\delta_{CP}(\text{true}) = 0$.

The solid green lines are what we expect from T2K+NO ν A+Reactor experiments, where we consider 5 years of running of T2K in the neutrino mode alone, while the dashed green lines are for the case when T2K is run for 2.5 years in the neutrino mode and 2.5 years in the antineutrino mode. A comparison of the potential of PINGU versus the LBL+Reactor data shows that for the true normal hierarchy case, just 3 years of data from PINGU alone has a sensitivity to the octant of θ_{23} comparable to that of the combined long baseline and reactor data. For values of $\sin^2\theta_{23}(\text{true})$ closer to maximal mixing, the PINGU alone analysis suffers mainly from marginalization over θ_{23} in the fit, while for values far away from maximal mixing, especially on the low octant side, the PINGU sensitivity is constrained mainly from the uncertainty in θ_{13} and the neutrino mass hierarchy. This was demonstrated earlier in Fig. 2. As a result, with the reactor data added the sensitivity from PINGU improves further for these values of $\sin^2\theta_{23}(\text{true})$ and for true normal hierarchy. Adding the long baseline data helps constrain $\sin^2 2\theta_{23}$ and Δm_{eff}^2 better. This synergy results in better sensitivity from the combined analysis of PINGU with T2K, NO ν A and reactor experiments, and the combined $\Delta\chi^2$ is higher than the simple sum of the $\Delta\chi^2$ from PINGU and the long baseline and reactor experiments. The combined $\Delta\chi^2$ is shown by the red lines in the figure. The solid red line is for T2K running for 5 full years in the neutrino mode while the dashed red lines are for T2K running for 2.5 years in the neutrino mode and 2.5 years in the antineutrino mode. For normal hierarchy, the combined data set including 3 years of PINGU will return a $\Delta\chi^2 > 16$ if $\sin^2\theta_{23}(\text{true}) < 0.426$ and > 0.586 , and $\Delta\chi^2 > 25$ if $\sin^2\theta_{23}(\text{true}) < 0.413$. For the inverted hierarchy, as discussed before, the octant sensitivity of PINGU is low. On combining with the T2K, NO ν A and reactor data we expect $\Delta\chi^2 > 9$ if $\sin^2\theta_{23}(\text{true}) < 0.43$ and > 0.585 , and $\Delta\chi^2 > 16$ if $\sin^2\theta_{23}(\text{true}) < 0.417$.

Finally, we have checked that the $\Delta\chi^2$ for the wrong octant from PINGU grows almost linearly with the number of years of running of the experiment. We have presented all results in this paper for a very short running time of only 3 years. But as this experiment accumulates more data, the statistical significance with which it can diagnose the true octant of θ_{23} will grow.

5 Conclusions

In this paper we explored the prospects of determining the octant of θ_{23} with atmospheric neutrinos at PINGU. For illustration, we simulated 3 years of data at this experiment with some benchmark detector specifications. We used the effective volume of the detector read from [38] for the curve labelled “Triggered Effective Volume, R=100m”. For the energy and angle resolutions of the neutrino, we used some benchmark values consistent with that used in the literature. We used Gaussian function for the resolution functions with our optimal choice for the width of these Gaussians being $\sigma_E = 0.2E'$ and $\sigma_\Theta = 0.5 (1 \text{ GeV}/\sqrt{E'})$ for the energy and angle resolution, respectively. We studied the impact of the worsening of the resolutions, both in energy and angle. We defined a χ^2 and showed the statistical significance with which the octant of θ_{23} can be determined with just 3 years of running of PINGU. In our analysis we included 5 systematic uncertainties, 4 of which come from uncertainties in the theoretical fluxes. We showed in detail the impact of systematic uncertainties on the final χ^2 from PINGU. The systematic uncertainties were seen to make a huge impact on the sensitivity, with the χ^2 reducing by as much as a factor of 3.5 to 7.5, depending on the energy and angle resolutions chosen. Therefore, we conclude that the inclusion of systematic uncertainties on the theoretical fluxes is a must for any PINGU analysis.

We also looked at the impact of the uncertainties on the neutrino oscillation parameters. We presented results where the wrong octant χ^2 from PINGU alone was marginalized over all oscillation parameters, including the neutrino mass hierarchy. The effect of marginalizing over θ_{23} was seen to be dominant for both true normal as well as true inverted hierarchy. The effect of θ_{13} , $|\Delta m_{\text{eff}}^2|$ and the neutrino mass hierarchy was seen to be dominant for the true normal hierarchy and lower values of $\sin^2\theta_{23}(\text{true})$. The inclusion of the prospective 3 years of running of the Daya Bay, RENO and Double Chooz reactor data was shown to alleviate the problem from parameter uncertainties in this region by severely constraining the allowed range of θ_{13} . We found that for the true normal hierarchy, with just 3 years of PINGU data *alone*, one could rule out the wrong hierarchy at the 2σ C.L. for $\sin^2\theta_{23}(\text{true}) < 0.427$ and > 0.569 . With addition of the data from the reactor experiments, we could achieve 3σ C.L. determination of the octant for $\sin^2\theta_{23}(\text{true}) < 0.419$ and > 0.586 for the true normal hierarchy. The sensitivity of PINGU to the octant of θ_{23} is shown to be rather low for the true inverted hierarchy. The $\Delta\chi^2$ for the wrong hierarchy goes linearly with the statistics in this regime. Hence the sensitivity will go up as we increase the number of year of running of PINGU.

We also looked in detail at the prospects of measuring the octant of θ_{23} at the long baseline experiments T2K and NO ν A in conjunction with the reactor data which synergetically determines the value of θ_{13} in a clean way. The NO ν A configuration has been re-optimized by the collaboration following the measurement of θ_{13} . Though the T2K experiment is still slated to run only in the neutrino mode for the full 5 years, there have been recent studies looking to re-optimize the T2K run by introducing a few years of antineutrino running for this experiment. In this paper, we looked at the physics reach of

both old as well as new $\text{NO}\nu\text{A}$, and T2K run in both the 5 years in the neutrino mode and 2.5 years of neutrino and 2.5 years in the antineutrino mode. We started by comparing the impact on the mass hierarchy sensitivity due to the change of the $\text{NO}\nu\text{A}$ and T2K configurations. We showed that while the new $\text{NO}\nu\text{A}$ configuration improves the mass hierarchy sensitivity for the entire range of $\delta_{CP}(\text{true})$, running the T2K in the 2.5+2.5 years of neutrino plus antineutrino mode results in a small reduction of the mass hierarchy sensitivity. We next looked at the octant sensitivity from these experiments along with the reactor experiments, and again we made a comparative study of the new vs old $\text{NO}\nu\text{A}$ and T2K. As pointed out in the literature before, we found that the addition of the antineutrino run in the T2K data helps in cancellation of the octant- δ_{CP} degeneracy. As a result, in regions of $\delta_{CP}(\text{true})$ where the combined sensitivity of T2K, $\text{NO}\nu\text{A}$ and the reactors to the octant is low, the addition of the antineutrino run improves the sensitivity to the octant of θ_{23} .

Finally, we added 3 years of projected PINGU data to the projected data from T2K, $\text{NO}\nu\text{A}$ and the reactors and showed the results both as a function of $\delta_{CP}(\text{true})$ as well as $\sin^2\theta_{23}(\text{true})$. Three years of PINGU data along with data from T2K, $\text{NO}\nu\text{A}$ and the reactors will be able to pin down the right octant of θ_{23} for the true normal hierarchy to better than 4σ C.L. for all values of $\sin^2\theta_{23}(\text{true}) < 0.426$ and > 0.586 . A 5σ significance for the right octant can be achieved if $\sin^2\theta_{23}(\text{true}) < 0.413$ for the true normal hierarchy. If the inverted hierarchy were true, then we would have a 3σ determination of octant of θ_{23} for $\sin^2\theta_{23}(\text{true}) < 0.43$ and > 0.585 from the combined data set with of 3 years of PINGU. The sensitivity will scale as we increase the number of years of running of the PINGU experiment and the $\Delta\chi^2$ coming from PINGU increases almost linearly with the number of years of running of this experiment.

Acknowledgements

We thank S. Prakash for discussions. S.C. acknowledges partial support from the European Union FP7 ITN INVISIBLES (Marie Curie Actions, PITN-GA-2011-289442).

References

- [1] D. J. Koskinen, Mod. Phys. Lett. A **26**, 2899 (2011).
- [2] For details of the IceCube experiment see *icecube.wisc.edu*
- [3] M. G. Aartsen *et al.* [IceCube Collaboration], Phys. Rev. Lett. 111, **081801** (2013) [arXiv:1305.3909 [hep-ex]].
- [4] T. IceCube [PINGU Collaboration], arXiv:1306.5846 [astro-ph.IM].
- [5] E. K. .Akhmedov, S. Razzaque and A. Y. .Smirnov, JHEP **1302**, 082 (2013) [JHEP **1302**, 082 (2013)] [Erratum-ibid. **1307**, 026 (2013)] [arXiv:1205.7071 [hep-ph]].
- [6] M. Ribordy and A. Y. Smirnov, Phys. Rev. D **87**, 113007 (2013) [arXiv:1303.0758 [hep-ph]].
- [7] S. K. Agarwalla, T. Li, O. Mena and S. Palomares-Ruiz, arXiv:1212.2238 [hep-ph].
- [8] W. Winter, Phys. Rev. D **88**, 013013 (2013) [arXiv:1305.5539 [hep-ph]].

- [9] M. Blennow and T. Schwetz, arXiv:1306.3988 [hep-ph].
- [10] S. -F. Ge, K. Hagiwara and C. Rott, arXiv:1309.3176 [hep-ph].
- [11] H. Minakata, H. Sugiyama, O. Yasuda, K. Inoue and F. Suekane, Phys. Rev. D **68**, 033017 (2003) [Erratum-ibid. D **70**, 059901 (2004)] [hep-ph/0211111]; K. Hiraide, H. Minakata, T. Nakaya, H. Nunokawa, H. Sugiyama, W. J. C. Teves and R. Z. Funchal, Phys. Rev. D **73**, 093008 (2006) [hep-ph/0601258].
- [12] K. B. M. Mahn and M. H. Shaevitz, Int. J. Mod. Phys. A **21**, 3825 (2006) [hep-ex/0409028].
- [13] P. Huber, M. Lindner, T. Schwetz and W. Winter, JHEP **0911**, 044 (2009) [arXiv:0907.1896 [hep-ph]].
- [14] S. K. Agarwalla, S. Prakash and S. U. Sankar, JHEP **1307**, 131 (2013) [arXiv:1301.2574 [hep-ph]].
- [15] A. Chatterjee, P. Ghoshal, S. Goswami and S. K. Raut, JHEP **1306**, 010 (2013) [arXiv:1302.1370 [hep-ph]].
- [16] M. C. Gonzalez-Garcia, M. Maltoni and A. Y. Smirnov, Phys. Rev. D **70**, 093005 (2004) [hep-ph/0408170].
- [17] S. Choubey and P. Roy, Phys. Rev. D **73**, 013006 (2006) [hep-ph/0509197].
- [18] D. Indumathi, M. V. N. Murthy, G. Rajasekaran and N. Sinha, Phys. Rev. D **74**, 053004 (2006) [hep-ph/0603264].
- [19] A. Samanta and A. Y. Smirnov, JHEP **1107**, 048 (2011) [arXiv:1012.0360 [hep-ph]].
- [20] K. Abe, T. Abe, H. Aihara, Y. Fukuda, Y. Hayato, K. Huang, A. K. Ichikawa and M. Ikeda *et al.*, arXiv:1109.3262 [hep-ex].
- [21] V. Barger, R. Gandhi, P. Ghoshal, S. Goswami, D. Marfatia, S. Prakash, S. K. Raut and S U. Sankar, Phys. Rev. Lett. **109**, 091801 (2012) [arXiv:1203.6012 [hep-ph]].
- [22] A. Blake, H. Gallagher, talk at ISOUP, May 26, 2013.
- [23] P. Coyle et al. [The Km3Net collaboration], contribution to the European Strategy Preparatory Group Symposium, September 2012 Krakow, Poland.
- [24] Y. Itow *et al.* [T2K Collaboration], hep-ex/0106019.
- [25] P. A. N. Machado, H. Minakata, H. Nunokawa and R. Z. Funchal, arXiv:1307.3248 [hep-ph].
- [26] R. Petterson, talk at Neutrino 2012 Conference, June 2-9, 2012, Kyoto, Japan, <http://neu2012.kek.jp>
- [27] F. P. An *et al.* [DAYA-BAY Collaboration], Phys. Rev. Lett. **108**, 171803 (2012) [arXiv:1203.1669 [hep-ex]].
- [28] J. K. Ahn *et al.* [RENO Collaboration], Phys. Rev. Lett. **108**, 191802 (2012) [arXiv:1204.0626 [hep-ex]].

- [29] Y. Abe *et al.* [DOUBLE-CHOOZ Collaboration], Phys. Rev. Lett. **108**, 131801 (2012) [arXiv:1112.6353 [hep-ex]].
- [30] K. Abe *et al.* [T2K Collaboration], Phys. Rev. Lett. **107**, 041801 (2011) [arXiv:1106.2822 [hep-ex]].
- [31] P. Adamson *et al.* [MINOS Collaboration], Phys. Rev. Lett. **107**, 181802 (2011) [arXiv:1108.0015 [hep-ex]].
- [32] S. K. Agarwalla, S. Prakash, S. K. Raut and S. U. Sankar, JHEP **1212**, 075 (2012) [arXiv:1208.3644 [hep-ph]].
- [33] D. S. Ayres *et al.* [NOvA Collaboration], hep-ex/0503053.
- [34] X. Guo *et al.* [Daya-Bay Collaboration], hep-ex/0701029.
- [35] J. K. Ahn *et al.* [RENO Collaboration], arXiv:1003.1391 [hep-ex].
- [36] F. Ardellier, I. Barabanov, J. C. Barriere, M. Bauer, L. B. Bezrukov, C. Buck, C. Cattadori and B. Courty *et al.*, hep-ex/0405032.
- [37] M. Honda, T. Kajita, K. Kasahara and S. Midorikawa, Phys. Rev. D **70**, 043008 (2004) [astro-ph/0404457].
- [38] D. Cowan, talk at Snowmaa Cosmic Frontier Workshop, March 6-8, 2013, SLAC, USA, <http://>
- [39] A. M. Dziewonski and D. L. Anderson, Phys. Earth Planet. Interiors **25**, 297 (1981); S. V. Panasyuk, Reference Earth Model (REM) webpage, <http://cfauves5.harvard.edu/lana/rem/index.html>.
- [40] P. Huber, J. Kopp, M. Lindner, M. Rolinec and W. Winter, Comput. Phys. Commun. **177**, 432 (2007) [hep-ph/0701187]; P. Huber, M. Lindner and W. Winter, Comput. Phys. Commun. **167**, 195 (2005) [hep-ph/0407333].
- [41] A. Ghosh, T. Thakore and S. Choubey, JHEP **1304**, 009 (2013) [arXiv:1212.1305]; A. Ghosh and S. Choubey, arXiv:1306.1423 [hep-ph].
- [42] A. Ghosh and S. Choubey, in preparation.